WATER SUPPLY DIVISION.

Dated 4th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 21st November 1930, till 1 P.M., for removing the last 4" section of delivery main and replacing 5" cast iron pipe and old 6" cast iron existing pipes in parts for Improvements of Chikmagalur Town Water Supply. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th March 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Water Supply Division between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for removing the last 4" section of delivery main and replacing with 5" cast iron pipe and old 6" cast iron existing pipes in parts for Improvements to Chikmagalur Town Water Supply," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for removing the last 4" section of delivery main and replacing with 5" cast iron pipe and old 6" cast iron existing pipes in parts for Improvements of Chikmagalur Town Water Supply.

No.	Items of work	Per	Quantity
	LABOUR.		
1	Removing and hoisting up, cleaning, conveying and stacking at the Town Municipal Stores 4" cast iron pipes.	R.ft.	3,969
2	Laying and cement jointing 5" cast iron new pipes including cuts and collar joints.	Each	200
3	Laying and lead jointing the new 5" cast iron pipes ...	,,	25
4	Cleaning, coating with boiled tar conveying and laying existing 6" cast iron pipe.	R.ft.	2,007
5	Cement jointing 6" cast iron pipes including cuts and collar joints.	Each	150
6	Lead jointing do do do ...	,,	75
7	Lead or flange jointing 4" cast iron specials	,,	4
8	Removing and fixing A. V. in position	,,	1
9	Earthwork excavation and refilling pipe trench from 0' to 5' depth.	C.yd.	2,631
10	Do do do 5' to 6' depth ...	,,	405
11	Do do do 6' to 7' do ...	,,	302
12	Do do do 7' to 8' do ...	,,	69
13	Do do do 8' to 9' do ...	,,	37
14	Do do do 9' to 10' do ...	,,	22
15	Do do do 10' to 11' do ...	,,	22
16	Do do do 11' to 12' do ...	,,	11
17	Carting 5" cast iron pipe and specials from Kadur Railway Station to Chikmagalur site of work nearly 30 miles.	cwt.	446

Abstract Notification dated 23rd—25th October 1930.

The attention of the public is invited to the detailed notification, calling for sealed tenders for laying 4" cast iron delivery and distribution pipes for Water Supply to the Northern Extension and Kuripalya at Tumkur published on page 1350 of Part VI of the *Mysore Gazette*, dated 30th October 1930.

The last day for the receipt of tenders is 14th November 1930.

M. NARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Notice dated 28th October 1930.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, pages 1377 and 1378, calling for tenders for Resorting Thimmnahalli Kanivekere Reg. No. 858, Bagepalli Taluk

The latest date for tender is 25th November 1930.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 25th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 24th November 1930 (3 P.M.), for restoring Neglal Tank, Reg. No. 232 of Koratagere Taluk, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Negeal Tank, Reg. No. 232 of Koratagere Taluk, Tumkur District" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender of the successful competitor will be required to execute the usual bond in defaults of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.